


BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B**Improvements RCC Road and Drain in surrounding area in Ward No.05 Byatarayanapura Sub Division**

SNo	Quantity	Item Name	Unit	Approved Rates of K R Santhosh Kumar	
				In figures	In words
1	2620.30	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all lead and lift, loading and unloading and all other incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Cum	217.94	Rupees Two Hundred Seventeen And Paise Ninety Four Only
2	328.50	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. with all lead and lift, loading and unloading and all other incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Cum	5691.91	Rupees Five Thousand Six Hundred Ninety One And Paise Ninety One Only
3	44.00	KSRB 4-6.1: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.1 with all lead and lift, loading and unloading and all other incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	287.10	Rupees Two Hundred Eighty Seven And Paise Ten Only
4	352.00	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surfaces such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 with all lead and lift, loading and unloading and all other incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	398.38	Rupees Three Hundred Ninety Eight And Paise Thirty Eight Only


Contractor


Executive Engineer
Project Division
Yelahanka Zone

Quantity	Item Name	Unit	Approved Rates of K R Santhosh Kumar		
			In figures	In words	
5	610.80	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications do-Wall and Bottom Thickness 10cm with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Cum	7635.95	Rupees Seven Thousand Six Hundre Thirty Five And Paise Ninety Five Only
6	61.60	Providing and laying cement concrete using 20mm and downsize granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for RCC works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exclusive of cpost of steel and fabricaton charges) Ready Mixed Cement Concrete M 20 for Raft foundation, Column, Footing, main and secondary beams. with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Cum	6058.02	Rupees Six Thousand Fifty Eight And Paise Two Only
7	39.14	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. Specificatiowith all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	MT	75928.86	Rupees Seventy Five Thousand Nine Hundred Twenty Eight And Paise Eighty Six Only
8	2443.20	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of all materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	2453.38	Rupees Two Thousand Four Hundred Fifty Three And Paise Thirty Eight Only
9	154.00	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of all materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer inchargewith all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	5687.82	Rupees Five Thousand Six Hundred Eighty Seven And Paise Eighty Two Only


Contractor


Executive Engineer
Project Division
Yelahanka Zone

Sl. No.	Quantity	Item Name	Unit	Approved Rates of K R Santhosh Kumar	
				In figures	In words
10	1722.00	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specification No.301 Loading and unloading with 10km lead with all lead and lift, loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Cum	59.06	Rupees Fifty Nine And Paise Six Only
11	968.63	KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications with all lead and lift, loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Cum	2100.94	Rupees Two Thousand One Hundred And Paise Ninety Four Only
12	4305.00	KSRRB M 500-6, Providing and applying primer coat with SS bitumen emulsion on prepared surface of granular Base such as WBM WMM including clearing of road surface and spraying primer at the rate of 0.60 kgsqm using mechanical means complete as per specifications. As per MORTH with all lead and lift, loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	31.16	Rupees Thirty One And Paise Sixteen Only
13	8610.00	KSRRB M500-7 : Providing and applying tack coat using 80/100 grade bitumen (VG10) on prepared black topped surfaces at 2.5 Kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH / Chapter 5 with all lead and lift, loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	13.35	Rupees Thirteen And Paise Thirty Five Only
14	215.25	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 505 of MORTH V revision using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen with all lead and lift, loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Cum	7199.74	Rupees Seven Thousand One Hundred Ninety Nine And Paise Seventy Four Only


Contractor


Executive Engineer
Project Division
Yelahanka Zone
5/3/21

Sl. No.	Quantity	Item Name	Unit	Approved Rates of K R Santhosh Kumar	
				In figures	In words
15	172.20	KSRRB M500-19. Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 507 of MORTH V revision using 40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 45 mm) with 5.4% VG-30 Bitumen with all lead and lift, loading and unloading and all other incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Cum	8305.85	Rupees Eight Thousand Three Hundred Five And Paise Eighty Five Only
16	102.50	KSRRB M800-13. Road Marking with Hot Applied Thermoplastic Compound with Reflecting Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 with all lead and lift, loading and unloading and all other incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	477.39	Rupees Four Hundred Seventy Seven And Paise Thirty Nine Only
17	1822.00	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete with all lead and lift, loading and unloading and all other incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	No	454.02	Rupees Four Hundred Fifty Four And Paise Two Only
18	287.00	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 with all lead and lift, loading and unloading and all other incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	110.16	Rupees One Hundred Ten And Paise Sixteen Only
19		GST @ 12%			

Subin Dm
Contractor

H.V. J
Executive Engineer
Project Division
Yelahanka Zone
17/3/20